

LIST OF STREETS**Preliminary Street List and Repair Method**

Street	From	To	Avg. Width (ft)	Approx. Length (ft)	Pavement Thickness (in)	Repair Method	Notes
PICARD LN	VARNEY RD	END	24	1725	1.5	Full-Width Mill & 1.5" overlay (1/2" mix)	
CARRAIGE HILL DR	PICARD LN	END	24	369.3	1.5	Full-Width Mill & 1.5" overlay (1/2" mix)	
ATINA WAY	TOLEND RD	END	18	575	4	Reclaim & 4" repave	
TOLEND RD	COLUMBUS AVE	WASHINGTON ST	28	2800	1.5	1.5" overlay (1/2" mix)	Edge mill curb side; bridge not to be paved
GLEN HILL RD	TOLEND RD	COVERED BRIDGE LN	24	3300	1.5	1.5" overlay (1/2" mix)	
DURHAM RD	MAST RD	BRIDGE	32	5500	1.5	1.5" overlay (1/2" mix)	Edge mill curb side; to be completed between late June and early August
BELLAMY RD	DURHAM RD	ALUMNI DR	24	2700	1.5	Edge Mill & 1.5" overlay (1/2" mix)	To be completed between late June and early August
PONDVIEW	MAST RD	END	28	1100	1.5	Full-Width Mill & 1.5" overlay (1/2" mix)	
INDUSTRIAL PARK DR	LITTLEWORTH RD (S)	LITTLEWORTH RD (N)	38	4200	1.5	Full-Width Mill & 1.5" overlay (1/2" mix)	
WATERLOO CIR	DOVER NECK RD (N)	DOVER NECK RD (S)	24	2500	1.5	Full-Width Mill & 1.5" overlay (1/2" mix)	
ATLANTIC AVE	PORTLAND AVE	GULF RD	24	2150	1.5	Full-Width Mill & 1.5" overlay (1/2" mix)	
ESSEX ST	PORTLAND AVE	END	22	625	1.5	Full-Width Mill & 1.5" overlay (1/2" mix)	
HANCOCK ST	PORTLAND AVE	FOREST ST	28	380	1.5	Full-Width Mill & 1.5" overlay (1/2" mix)	
FOREST ST	END	END	24	1600	1.5	Full-Width Mill & 1.5" overlay (1/2" mix)	
HIGHLAND	ROLLINS RD	17 HIGHLAND	19	900	1.5	1.5" overlay (1/2" mix)	
HALE ST	LOCUST ST	CENTRAL AVE	40	300	1.5	Edge Mill & 1.5" overlay (1/2" mix)	
LOCUST ST	KIRKLAND ST	HALE ST	34	425	1.5	Edge Mill & 1.5" overlay (1/2" mix)	
TRAKEY ST	LOCUST ST	CENTRAL AVE	30	500	4	Pave gravel road	To be completed after utility project; granite curb to be added to south side
RICHMOND ST	W CONCORD ST	WASHINGTON ST	24	625	4	Pave gravel road	To be completed after utility project
W CONCORD ST	ARCH ST	LEXINGTON ST	28	750	1.5	Edge Mill & 1.5" overlay (1/2" mix)	
TOWLE AVE	SILVER ST	CLIFFORD ST	30	440	1.5	1.5" overlay (1/2" mix)	To be completed between late June and early August
ANGLE ST	ACADEMY ST	CENTRAL AVE	24	300	1.5	1.5" overlay (1/2" mix)	
WENTWORTH TER	SPAULDING TURNPIKE	LIMITS (N)	16	675	4	Reclaim & 4" repave	
WENTWORTH TER	WENTWORTH TER	LIMITS (S)	16	300	4	Pave gravel road	
CHANDLER WAY	WEST KNOX MARSH RD	OLD LITTLEWORTH RD	22	990	1.5	Full-Width Mill & 1.5" overlay (1/2" mix)	
BEVERLY LN	CHANDLER WAY	END	32	770	1.5	Full-Width Mill & 1.5" overlay (1/2" mix)	
WEST KNOX MARSH RD	KNOX MARSH RD	END	24	900	4	Reclaim & 4" repave	

LIST OF STREETS**Preliminary Street List - Estimated Quantities per Street**

Item Description	Crushed Gravel for Shoulder Leveling	Reclaimed Stabilized Base Processed in Place, 8" Deep	HBP – ¾" Binder Mix, Machine Method	HBP – ½" Surface Mix, Machine Method	HBP – Hand Method	Pavement Joint Adhesive	Cold Planing Bituminous Surfaces	Cold Planing Bituminous Surfaces - Driveways	Adjust Catch Basin or Manhole Covers	Reconstructing/Adjusting Manhole Holes	Straight Granite Curb	Straight Granite Slope Curb	Reset Granite Curb	Bituminous Curb, Type A	Adjusting Water Gates and Shutoffs	Pavement Marking Recording (Subsidiary)
Item #	304.32	306.108	403.11023	403.11043	403.12	403.16	417	417.9	604.45	604.5	609.01	609.21	609.5	609.812	611.9	-
Units	Ton	SY	Ton	Ton	Ton	LF	SY	LF	EA	LF	LF	LF	LF	LF	EA	-
PICARD LN	100			393		1725	4600	242	0						0	N
CARRAIGE HILL DR	21			84		369.3	985	198	1						0	N
ATINA WAY	33	1150	164	98		1150	0	132	1						2	N
TOLEND RD	81			745		2800	2178	462	27						7	Y
GLEN HILL RD	191			752		3300	0	330	4						12	N
DURHAM RD	159			1672		5500	4278	1100	54						25	Y
BELLAMY RD	0			616		2700	4200	880	26						11	Y
PONDVIEW	0			293		1100	3422	264	7						1	N
INDUSTRIAL PARK DR	243			1516		4200	17733	2250	22						15	N
WATERLOO CIR	0			570		2500	6667	550	37						6	N
ATLANTIC AVE	124			490		2150	5733	726	26						12	Y
ESSEX ST	0			131		625	1528	308	5						1	N
HANCOCK ST	0			101		380	1182	176	4						1	N
FOREST ST	0			365		1600	4267	836	22						7	N
HIGHLAND	52			162		900	0	198	0						0	N
HALE ST	0			114		300	467	60	4						0	Y
LOCUST ST	0			137		425	661	88	11						5	Y
TRAKEY ST	29		238	143		1000	0	60	3		240				0	N
RICHMOND ST	36		238	143		1250	0	330	5						1	N
W CONCORD ST	0			200		750	1167	374	6						2	N
TOWLE AVE	0			125		440	1467	176	12						2	Y
ANGLE ST	0			68		300	0	175	2						2	N
WENTWORTH TER	39	1200	171	103		1350	0	120	8						3	N
WENTWORTH TER	17		76	46		600	0	0	1						1	N
CHANDLER WAY	57			207		990	2420	264	9						4	N
BEVERLY LN	45			234		770	2738	154	5						2	N
WEST KNOX MARSH RD	52	2400	342	205		1800	0	132	5						5	N