Appendix H

Application Form

APPLICANT INFORMATION	
Name of Local Government Entity:	City of Dover, NH
Federal ID Number:	02-6000230
D-U-N-S Number: (Applicant must apply and have number by 3/1/2010)	099359168
Applicant has registered with the Central Contractor Registration (CCR)	☒ Yes ☐ No
If Partnering, have all Partnership Agreement Forms been included?	☐ Yes ☐ No

CONTACT INFORMATION Enter the primary contact at the Applicant Organization for this Application	
Applicant Primary Contact Name:	Rick Jones
Applicant Primary Contact Title:	CD Coordinator
Address:	288 Central Ave.
City, State, Zip Code + 4:	Dover, NH 03820-4169
Office Phone:	516-6034
Cell Phone:	
Fax:	516-6007
E-Mail Address:	r.jones@ci.dover.nh.us
APPLICANT ELIGIBILITY CHECKLIST	
Applicant is a Local Government located in New Hampshire.	☒ Yes ☐ No (applicant is not eligible)

Project Category (select one) and fill in requested information.				
☒ Lighting Upgrades	estimated annual MMBTU source energy reduced	=	74	MMBTU
☐ Building Energy Efficiency Measures	estimated annual MMBTU source energy reduced	=		MMBTU
☐ Building Energy Audits	square footage of the facilities to be audited	=		sqft
☐ Energy Studies and Energy Planning	population affected	=		people
☐ Reducing Commuter Vehicle Fuel Use	estimated annual gallons of fuel saved	=		gallons
☐ Idling Reduction Technologies	estimated annual gallons of fuel saved	=		gallons
☐ Waste Reduction	annual tons of waste reduced	=		tons
☐ Renewable Energy	estimated annual MMBTU energy generated	=		MMBTU
☐ Other Innovative Projects	Describe conservation benefits of project in project description			

PRIMARY PLACE OF PERFORMANCE Enter the physical location of the project. For projects with multiple locations, use the location with the largest dollar amount of measures.	
Location Name:	McConnell Center
Address:	63 Locust Street
City, State, Zip Code + 4:	Dover, NH 03820-4169
Region number: (Refer to Appendix D)	03

PROGRESS PAYMENTS Select one
☒ Applicant requests award payment in 2 parts. At equipment delivery and/or 50% of services provide and at project completion.
☐ Applicant request award payment in 1 part. At project completion.

Federal Certifications	
For any member of the Application team, have you received, or do you expect to receive, over $500,000 of Federal awards for any of the fiscal years during the term of our agreement? If yes, you are required to obtain an independent audit pursuant to the Federal Office of Management and Budget, OMB circular A-133, and provide a copy to OEP throughout the term of this Agreement.	☒ Yes ☐ No
Did your organization receive: (1) more than 80% of its annual gross revenues in Federal awards, (2) 25 million or more in annual gross revenues from Federal awards, and (3) the public does not have access to information about the compensation of the senior executives under filing requirements of the Security Exchange Act of 1934 or 780(d) or section 6104 of the Internal Revenue Code? If yes, provide the names and compensation of the five most highly compensated officers.	☐ Yes ☒ No

Proposed Project	
Brief Project Description: Lighting upgrades at the McConnell Center	
Cost of the Project:	$134,100
Funds Requested:	$134,100

AUTHORIZING SIGNATURE

I have read, understood and am in compliance with all rules and regulations concerning this incentive program. I certify that all information provided is correct to the best of my knowledge. I allow reasonable access to my property to inspect the installation and performance of the technologies and installations that are eligible for incentives under this Application. Furthermore, I understand that the project is to be funded under ARRA and that additional reporting and other requirements will apply, including, but not limited to: jobs reporting requirements, Buy American, and Federal Davis-Bacon prevailing wage requirements; and other requirements as may be imposed by Federal or State oversight entities. I agree to provide to OEP any and all required materials, documentation, access to facilities, and other required information, on the schedule required by OEP to meet all requirements. I understand that this project may be audited for compliance with the requirements of this Application. I understand that failure to comply with ARRA requirements and to complete the Project by March 10, 2012 may result in loss of funding.

This Application must be signed by an authorized designee of the eligible entity. Service providers or vendors may not sign this Application.

Signature:	Date: 2/11/10
Printed Name: J.Michael Joyal,Jr.	Title: Dover City Manager

Acknowledgement: State of New Hampshire County of Strafford

On 2/11/10, before the undersigned officer, personally appeared the person identified in signature block above, or satisfactorily proven to be the person whose name is signed in signature block above, and acknowledged that s/he executed this document in the capacity indicated in the signature block.

Signature of Notary Public or Justice of the Peace

[SEAL] Colleen E. A. Bessette

COLLEEN E. A. BESSETTE, Notary Public
My Commission Expires October 22, 2013

Name and Title of Notary Public or Justice of the Peace

Colleen Bessette, Exec Assistant

DOVER'S COMMITMENT TO SUSTAINING ENERGY EFFICIENCY

This past January, The City of Dover entered into a Energy Services Agreement with Johnson Controls to perform energy upgrades to the City's Waste Water Treatment Plant.(WWTP)

The project involved replacing the existing power transformers and weatherization in the McConnell Center.with high efficiency transformers and balancing the existing heat pumps and thermostats for the building. These projects are being completed with a combination of direct EECBG funds, and CDBG-R funds. The project is a part of a master energy services contract that the City has with Johnson Controls and was separated from the other energy upgrades being performed by the city to comply with all of the ARRA funding requirements.

Due to budget constraints the total recommended energy efficiency improvements and renewable energy projects had to be scaled back. The lighting retrofit at the McConnell Center had to be scaled back due to the budget and overall project cost reduction measures required to get the energy services contract passed. The infusion of funding will allow all of the recommended improvements to be made to the McConnell Center.

The City has and is committed to replacing outdated equipment and making energy efficiency improvements to its buildings. The overall Energy Contract with Johnson Controls is just over $2.4 million dollars, with the majority coming from City bonding. The payback for the entire project is estimated at 7.21 years. The existing contract amount for the McConnell Center is $79,551. With the added lighting improvements, the project cost would go to $213,651. All of the tenants at the Center pay a square footage price for utilities. The improvements would reduce the annual utility bill of all the tenants of the building which are mostly human service agencies.

Although the City would like to do more projects than currently under contract, a combination of the payback length on some of the items, ineligibility to use ARRA funding for other conservation measures and City spending limits implemented by the voters forced us to curtail some of the desired projects. In addition, Dover has an Energy Advisory Committee that is fully supportive of this project.

McConnell Center
Lighting Fixture Retrofit & Controls Addendum

Detailed Description of Facility Improvement Measure

Johnson Controls has performed a survey of the interior lighting system at the McConnell Center and has found opportunities to capture energy savings, improve lighting quality and reduce maintenance costs.

As a result of the survey and analysis, Johnson Controls has developed a high efficiency lighting upgrade project that will provide the City of Dover with a retrofit of over 1,149 lighting fixtures and sensors resulting in an annual savings of 100,561 kWh, a reduction in electrical demand of 56.3 kW, cooling credit of 3,854 kWh and a heating debit of 74 MMBtu.

The following table summarizes the cost and savings:

Cost	$134,100
Expected Utility Incentives	$16,880
First Year Guaranteed Savings	$14,953

Existing Conditions

Lighting – Fixture Retrofit

The existing lighting system data utilized for this project was collected during site visits conducted by Johnson Controls in January 2010. The hours of operation of the various components of the lighting system, as listed, have been determined based on statements made by the City's representatives during interviews conducted by Johnson Controls subcontractors and personnel. The lighting demand (kW) per fixture, fixture quantities and recommended Facility Improvement Measures as listed, are based on the physical inspection of, and subsequent analysis by Johnson Controls.

In identifying the lighting improvement measure opportunities Johnson Controls has attempted to establish an accurate accounting of the various fixture styles, lamp and ballast types being used in the facility; the operating characteristics and various illumination requirements of the lighting system; long term energy and maintenance savings opportunities within the operating constraints of the existing system and immediate energy savings opportunities based on the impact of the Energy Policy Act of 1992 (EPACT).

The results of Johnson Controls' technical analysis indicate that the majority of energy savings opportunities result from conversion of existing T8 fixtures to more efficient lamps and ballasts. During the survey, opportunities were identified for the installation of occupancy sensors

Johnson Controls

© Johnson Controls, Inc. Do not copy (physically, electronically or in any other media) without the express written consent of Johnson Controls, Inc.

Lighting – Fixture Controls

In the McConnell Center, the lighting loads in the offices, corridors, mechanical rooms, administrative offices, stairwells and other areas are currently controlled utilizing standard one way or two-way wall switches. Opportunity exists to improve the overall operation of the facilities lighting systems through the installation of occupancy sensors.

Proposed Conditions

Lighting – Fixture Retrofit

Johnson Controls, Inc. proposes to retrofit the lighting systems with new high efficiency fixtures. The proposed lighting retrofits have been identified and are included with this Detailed Energy Audit as an Appendix. In general, JC will retrofit all fixtures that are candidates for retrofit/replacement with new fixtures or new lamps and ballast combinations. As such, lighting levels will be maintained at current levels with particular attention being paid to classroom areas.

The proposed lighting system shall:

1. Provide the most energy efficient lighting available on a retrofit or replacement basis, using state-of-the-art components and technology.
2. Exceed all Federal Energy Policy Act of 1992 (EPACT) lamp and luminaire efficiency standards.
3. Provide maintained light levels, which meet or exceed current Illuminating Engineering Society (IES) recommendations, while addressing particular illumination requirements for specific area and task functions.
4. Provide a quality of light conducive to a productive, safe and aesthetically pleasing environment. Specifically, issues of color rendition and uniformity of illumination shall be addressed.
5. Provide a reduction in future maintenance requirements through the standardization, extended life cycle and reduction in quantity of system components.

Lighting – Fixture Controls

In order to implement appropriate fluorescent lighting control throughout the included buildings, Johnson Controls recommends the installation of the following occupancy sensor:

> Type W- This is a dual technology sensor utilizing ultrasonic and passive infrared wall or ceiling switch sensor to be installed in small offices and various use areas. It will control 2-16 lighting fixtures, with loads ranging from 62 watts to 1000 watts.

In addition to the energy savings derived from the reduced operating hours, we assume that these occupancy sensors will reduce the fluorescent lighting kW demand. This presumes that there is a coincident factor of 20-30 percent of the controlled lights off at any time during on-

© Johnson Controls, Inc. Do not copy (physically, electronically or in any other media) without the express written consent of Johnson Controls, Inc.

peak hours. This is based on extensive practical experience in similar lighting control installations. Johnson Controls has not taken any credit for this demand reduction.

Savings Estimate

Savings Calculations

Savings calculations for lighting retrofits are generally calculated using the following methodology:

Baseline Energy Usage (kWh/yr)	=	Existing Fixture Watts x Operating Hours/yr x 1 kW/1000 Watts
Estimated Energy Usage (kWh/yr)	=	Proposed Fixture Watts x Op. Hours/yr x 1 kW/1000 Watts
Energy Savings (kWh/yr)	=	Baseline Energy Usage – Estimated Energy Usage

The following savings calculations represent the energy savings from the implementation of lighting controls on fixtures identified in the lighting table. For lighting controls, the baseline fixture watts for determining savings have been based on the post-retrofit fixture wattage.

Baseline Energy Usage (kWh/yr)	=	Baseline Fixture Watts x Operating Hours/yr x 1 kW/1000 Watts
Estimated Energy Usage (kWh/yr)	=	Proposed Fixture Watts x Operating Hours/yr x 1 kW/1000 Watts x % hours "off"
Energy Savings (kWh/yr)	=	Baseline Energy Usage – Estimated Energy Usage

Table XX-X: Energy Savings Summary

Savings Summary	
Water (kgal/yr)	
Water and Sewer ($/yr)	
Electricity (kWh/yr)	104,416
Electricity (kW)	56.3
Electricity ($/yr)	$15,997
Thermal Energy (MMBtu/yr)	(74)
Thermal Energy ($/yr)	(1044)
Total Savings ($/yr)	$14,953

Assumptions

The following specific assumptions were made:

- See calculations and line-by-line attached

Johnson Controls

© Johnson Controls, Inc. Do not copy (physically, electronically or in any other media) without the express written consent of Johnson Controls, Inc.

Operating Hours

In order to calculate the energy savings illustrated above, Johnson Controls relied on the kilowatt reduction achieved through its design and the facility's representation of the operating hours within the facility. Based on information gathered during interviews with the facility staff, an operating profile was determined to represent the majority of the lighting within the space considered for different areas. For area specific operating hours please refer to the room-by-room survey attached.

Scope of Work

A detailed listing of the fixtures proposed and room-by-room retrofits is included in the attached.

The lighting retrofit proposed for McConnell Center includes:

- Retrofit existing T8 fixtures with Super T8 electronic fixtures; provide tandem wiring double fixtures and reflectors according to the room-by-room table in the Appendix. A summary of each proposed retrofit is given in the Appendix.
  As a standard for installing T8 lamps, Johnson Controls will provide a high-grade "super saver" lamp that carries a higher color rendering index (CRI of 75 or greater) and higher lumen output per watt than the current T12 lamp type in use. Johnson Controls has specified a 4' F32 (28watt) 4,100K lamp that will pass the Federal guidelines relating to hazardous waste, specifically minimal mercury content, as the standard. It is due in part to the higher lumen per watt rating and the use of new lamps and ballasts that the light output from newly retrofitted fixtures will produce a higher foot-candle average than the existing system. In addition, due to the longer rated life and the ability of the T8 tri-phosphor lamp to maintain its lumen levels longer, there are ongoing maintenance savings attributable to the project.

- Installation of switch mounted, wall and ceiling mounted "dual technology" occupancy sensors as outlined.
- Retrofit of incandescent fixtures with compact fluorescent lamps as outlined.
- Removal of fixtures and de-lamping as outlined.

Exclusions

- None noted

Hazardous Waste Disposal

All necessary and appropriate barrels and containers for proper packaging of all PCB-containing ballasts and mercury-containing lamps removed are included as part of this project. Johnson Controls and its subcontractors will assume no liability in the generation, ownership or responsibility for hazardous waste material, except to assist in the coordination of the packaging of material removed. As part of this program, Johnson Controls has included the cost for handling, recycling and disposal of ballast and lamp waste.

© Johnson Controls, Inc. Do not copy (physically, electronically or in any other media) without the express written consent of Johnson Controls, Inc.

McConnell Center
Lighting Fixture Retrofit & Controls Addendum

February 4, 2010

Title	Lighting Fixture Retrofit and Controls
Date	February 5, 2010
District	Dover, NH
Building	McConnell Center

Summary *	Baseline	Proposed	Savings	$ Savings
kWh/yr			104,416	$11,203
kW			56.3	$4,793
MMBtu/yr			(74)	($1,044)
Total				$14,953

* *Includes both Lighting Retrofit & Lighting Controls*

Avg kWh	$0.11
$/MMBtu	$14.12

Measures	Units	Baseline	Cooling Credit	Heating Debit	Proposed	Energy Savings	Cost Savings ($)	Total Savings ($)
Lighting Fixture Retrofit	kWh					60,781	$6,521	$11,315
	kW					56.3	$4,793	
Lighting Fixture Controls	kWh					39,780	$4,268	$4,268
	kW					0.0	NA	
Total	kWh					104,416	$11,203	$14,953
	kW					56.3	$4,793	
	MMBtu					(74)	($1,044)	

YES Is Interaction Penalty Required ?

75%	...PERCENTAGE OF LIGHT HEAT RETURNED TO HVAC (%HTRET)	
56.29	...TOTAL KW LIGHTING LOAD REDUCTION (KWRED)	
100,561	...TOTAL KWH LIGHTING LOAD REDUCTION (KWHRED)	
36	...AVERAGE LIGHTING HOURS PER WEEK (LITEHRS)	= KWHRED/KWRED / WPY
12	... DEMAND MONTHS (CLGMONTHS)	
85%	...HEATING SYSTEM EFFICIENCY (EFF)	
1.10	....Avg. KW/TON OF CHILLER (KW/TON)	
	....AVG. KW/TON OF SUPPORT EQUIPMENT (KWSUPT)	
2,386	...HEATING HRS/YR FROM WEATHER DATA (HHPY)	
1,861	...COOLING HRS/YR FROM WEATHER DATA (CHPY)	
436	...WINTER HEATING COINCIDENT HRS (HTGCOHRS)	= MAX((HHPY / 168 - (52 WKS - WPY)),0) * LITEHRS
324	...SUMMER COOLING COINCIDENT HRS (CLGCOHRS)	= MAX((CHPY / 168 - (52 WKS - WPY)),0) * LITEHRS
50	...WEEKS/YEAR OF BUILDING OPERATION (WPY)	
90%	...PERCENT OF AREA AIR CONDITIONED (%COOLED)	

(Heating Debit)	(KWRED * 3413 * %HTRET * HTGCOHRS) / BTUs/UNIT / EFF ==========	(74) MMBTU
	FUEL SAVED * COST / MMBTU ==========	($1,044) $
(Cooling Credit)	(KWRED * 3413 * %HTRET * CLGCOHRS * %COOLED) / 12000 * KW/TON ==========	3,854 KWH
	MMBTU SAVED * COOLCOST ==========	$414 $
	TOTAL INTERACTION ==========	($630) $

Formulas:

Baseline Energy Usage (kWh/yr) = ∑(Existing Fixture Watts x Operating Hours/yr x 1 kW/1000 Watts)
Estimated Energy Usage (kWh/yr) = ∑(Proposed Fixture Watts x Op. Hours/yr x 1 kW/1000 Watts)
Energy Savings (kWh/yr) = Baseline Energy Usage – Estimated Energy Usage

Johnson Controls

© Johnson Controls, Inc. Do not copy (physically, electronically or in any other media) without the express written consent of Johnson Controls, Inc.

Fixture Locations

City of Dover - McConnell Building - A2

Dover, NH

Map	Location	Hours	Qty	Code	Notes
1	1st Floor - Men's Locker Room	3,750	1	CSS-120	W500A
1	1st Floor - Men's Locker Room	100	1	NOUPGRADE-18WPL	Existing 1 x 18W CF Recessed Can
1	1st Floor - Men's Locker Room	3,750	3	CDF-T8-QLXPS-UNV	
2	Women's Locker Room	3,750	3	CDF-T8-QLXPS-UNV	
2	Women's Locker Room	3,750	1	CSS-120	W500A
2	Women's Locker Room	100	1	NOUPGRADE-18WPL	Existing 1 x 18W CF Recessed Can
3	Dover Recreation Open Office Area	2,600	4	CDFT-T8-QLXPS-UNV	2 x 4 3L T8 Prismatic Troffer
3	Dover Recreation Open Office Area	2,600	1	CDF-T8-QLXPS-UNV	2 x 4 3L T8 Prismatic Troffer
4	Gary Bannon's Office	2,600	2	CDF-T8-QLXPS-UNV	
4	Gary Bannon's Office	2,600	1	WSS-120	WI1200 w/ Photocell
5	Laura R's Office	2,600	2	CDF-T8-QLXPS-UNV	
5	Laura R's Office	2,600	1	WSS-120	WI200 w/ Photocell
6	Room 122 - Paper Storage	1,000	1	WSS-120	
6	Room 122 - Paper Storage	1,000	2	UDF-T8-QXPS-UNV	
8	Room 119 - Custodian	1,000	1	A-T8-QLSS-UNV	
10	Boiler Room	1,000	8	A-T8-QLSS-UNV	
11	Room 103 - Storage	1,000	3	A-T8-QLSS-UNV	
11	Room 103 - Storage	1,000	1	WSS-120	
12	Room 101 - Dance Studio	2,000	8	CDF-T8-QLXPS-UNV	
12	Room 101 - Dance Studio	2,000	1	CSS-120	W1000A
13	Treadmill Area	2,600	4	CDF-T8-QLXPS-UNV	
13	Treadmill Area	2,600	1	CSS-120	CX105; Mount in Corner Near Brick Pillar Over Switch
14	Stationary Bike Area	2,600	3	BDFWW/N-T8-QXPS-UNV	Replacing 4L T8 Wide Wrap
14	Stationary Bike Area	2,600	1	CSS-120	
15	Weight Room	2,000	7	BDFWW/N-T8-QXPS-UNV	
15	Weight Room	2,000	1	CSS-120	W1000A
15	Weight Room	100	7	WIRE MOLD EXTENSION BOX	

Johnson Controls

© Johnson Controls, Inc. Do not copy (physically, electronically or in any other media) without the express written consent of Johnson Controls, Inc.

16	Universal Gym Area	100	7	WIRE MOLD EXTENSION BOX	
16	Universal Gym Area	2,000	7	BDFWW/N-T8-QXPS-UNV	
16	Universal Gym Area	2,000	1	CSS-120	W1000A
17	Fitness Center Corridor	3,750	9	UDF-T8-QXPS-UNV	
17	Fitness Center Corridor	3,750	3	NOUPGRADE-32WCF	Existing 1 x 32W CF Recessed Can
18	Elevator Alcove & Short Hallway	3,750	1	NOUPGRADE-4X18WPL	Existing 4 x 18W CF Surface Mount Fixture
18	Elevator Alcove & Short Hallway	3,750	2	NOUPGRADE-2'2LT5	Existing 2 x 2 2L 24W T5 Direct/Indirect
19	Reception Area	3,750	2	UDF-T8-QXPS-UNV	
19	Reception Area	3,750	2	NOUPGRADE-32WCF	Existing 1 x 32W CF Recessed Can
20	Office 114C	1,600	2	CDF-T8-QLXPS-UNV	
20	Office 114C	1,600	1	WSS-120	
21	Corridor	3,750	5	NOUPGRADE-2'2LT5	Existing 2 x 2 2L 24W T5 Direct/Indirect
21	Corridor	3,750	1	NOUPGRADE-32WCF	Existing 32W CF
22	Hallway Outside Dover Recreation Main Office	3,750	4	UDF-T8-QXPS-UNV	
22	Hallway Outside Dover Recreation Main Office	3,750	1	CSS-120	W1000A
23	Green Bean Kitchen Area	1,650	8	SLS20-I60-120	Replacing 60W Incandescent; Decorative Pendant Fixtures
23	Green Bean Kitchen Area	1,650	5	VRX32W-I100-120	Repl100W Inc in Jelly Jars; Surface Mt RAB Fixtr; Mount Directly to Box
23	Green Bean Kitchen Area	1,650	2	SLS20-I100-120	Replacing 100w Incandescent in Range Hood
24	Dry Goods Storage/Office	1,650	1	BDFWW/N-T8-QXPS-UNV	
24	Dry Goods Storage/Office	1,650	1	WSS-120	Requires 4 x 4 Raised Device Box Cover
26	Receiving Area	1,650	2	A-T8-QLSS-UNV	
28	Room 137 - Maintenance Office	1,650	2	UDF-T8-QXPS-UNV	
28	Room 137 - Maintenance Office	1,650	1	WSS-120	Requires 4 x 4 Raised Device Box Cover
29	Teen Center TV Area	2,600	5	CDF-T8-QLXPS-UNV	
29	Teen Center TV Area	2,600	1	CSS-120	W500A
30	Teen Center Open Area	2,200	14	CDF-T8-QLXPS-UNV	
30	Teen Center Open Area	2,200	2	CSS-120	W1000A
31	Teen Center Office	2,200	2	CDF-T8-QLXPS-UNV	
31	Teen Center Office	2,200	1	WSS-120	Requires 4 x 4 Square Raised Device Box Cover
31.1	Teen Center Office - Bathroom	2,200	1	NOUPGRADE-4'1L32WT8NP	Existing 4' 1L T8 Surface Mount Wrap
31.2	Teen Center Office - Rear Entry	1,600	1	CDF-T8-QLXPS-UNV	Existing 2 x 4 3L Prismatic Troffer

Johnson Controls

© Johnson Controls, Inc. Do not copy (physically, electronically or in any other media) without the express written consent of Johnson Controls, Inc.

31.3	Teen Center Office - Dry Goods Storage Area	1,000	1	CDF-T8-QLXPS-UNV	Existing 2 x 4 3L Prismatic Troffer
31.4	Teen Center Office - Unisex Bathroom	1,000	1	UDF-T8-QXPS-UNV	
31.5	Teen Center Music Area	2,200	14	CDF-T8-QLXPS-UNV	
31.5	Teen Center Music Area	2,200	2	CSS-120	W1000A
31.6	Teen Center - Unisex Bathroom	1,000	1	UDF-T8-QXPS-UNV	
31.7	Teen Center - Maintenance Room	1,000	2	CDF-T8-QLXPS-UNV	
32	Office	1,600	2	UDF-T8-QXPS-UNV	
32	Office	1,600	1	WSS-120	
33	Open Office Outside of Room 153	2,200	5	CDF-T8-QLXPS-UNV	
33	Open Office Outside of Room 153	2,200	1	CSS-120	W1000A
34.1	Office	1,600	2	CDF-T8-QLXPS-UNV	
34.1	Office	1,600	1	CSS-120	CX105
35	Supply Area	2,200	3	CDF-T8-QLXPS-UNV	
35	Supply Area	2,200	1	CSS-120	CX105
35.1	Door #7 - Vestibule	3,750	5	NOUPGRADE-2'2LT5	Existing 2 x 2 2L 24W T5 Direct/Indirect Fixture
35.1	Door #7 - Vestibule	3,750	7	NOUPGRADE-32WCF	Existing 1 x 32W CF Recessed Can
35.1	Door #7 - Vestibule	3,750	2	CSS-120	W500A
36	Storage Area	500	1	A1-T8-QLSS-UNV	
36.1	Entry Vestibule	100	6	NOUPGRADE-32WCF	Existing 32W CF Recessed Can
37	Dover Police Outreach Open Office Area	3,000	3	CDF-T8-QLXPS-UNV	
37	Dover Police Outreach Open Office Area	3,000	1	CSS-120	CX105
38	Outreach Office	3,000	4	CDF-T8-QLXPS-UNV	
38	Outreach Office	3,000	1	CSS-120	CX105
39	Office	1,600	1	CDF-T8-QLXPS-UNV	
40	Office	1,600	1	CDF-T8-QLXPS-UNV	
42	Dover Children's Center Reading Area	3,000	12	B-T8-QLSS-UNV	
42	Dover Children's Center Reading Area	3,000	2	CSS-120	W1000A
42.1	Dover Children's Center Reading Area	500	1	UDF-T8-QXPS-UNV	Restroom
43	Laundry Room	3,000	1	UDF-T8-QXPS-UNV	
43	Laundry Room	3,000	1	WSS-120	
44	Restroom	500	1	UDF-T8-QXPS-UNV	
45	Break Area	3,000	1	UDF-T8-QXPS-UNV	
45	Break Area	3,000	1	WSS-120	
46	Office 169	3,000	3	UDF-T8-QXPS-UNV	

Johnson Controls

© Johnson Controls, Inc. Do not copy (physically, electronically or in any other media) without the express written consent of Johnson Controls, Inc.

46	Office 169	3,000	1	WSS-120	
47	Room 171 Storage	2,000	1	WSS-120	
47	Room 171 Storage	2,000	4	UDF-T8-QXPS-UNV	
48	Rear Entry	1,600	2	UDF-T8-QXPS-UNV	
49	Room 173 - Conference	1,600	2	UDF-T8-QXPS-UNV	
49	Room 173 - Conference	1,600	1	WSS-120	
50	Room 164 - Dover Adult Learning Ctr. Child Care	1,600	5	UDF-T8-QXPS-UNV	
50	Room 164 - Dover Adult Learning Ctr. Child Care	1,600	1	WSS-120	Requires Combination 4 x 4 GFI/Switch Device Cover Plate
50	Room 164 - Dover Adult Learning Ctr. Child Care	100	1	PLATES	
50.1	Room 164 - Dover Adult Learning Ctr. Child Care	500	1	UDF-T8-QXPS-UNV	Restroom
50.2	Room 164 - Dover Adult Learning Ctr. Child Care	1,600	1	CSS-120	DT200 - Corner Mount Sensor w/ Photocell
50.2	Room 164 - Dover Adult Learning Ctr. Child Care	1,600	4	BDFWW/N-T8-QXPS-UNV	
50.3	Room 164 - Dover Adult Learning Ctr. Child Care	1,600	4	NO UPGRADE DUPLICATE	
50.3	Room 164 - Dover Adult Learning Ctr. Child Care	1,600	1	PHOTO	
51	Room #163	3,000	7	UDF-T8-QXPS-UNV	
51	Room #163	3,000	1	WSS-120	Requires Combination GFI/Switch Device Cover Plate
51	Room #163	100	1	PLATES	
51.1	Room #163	3,000	4	BDFWW/N-QXPS-UNV	Conduit Mounted; 9' AFF
51.1	Room #163	3,000	1	CSS-120	DT200 w/ Photo
51.2	Room #163	3,000	4	NO UPGRADE DUPLICATE	
51.2	Room #163	3,000	1	PHOTO	
52	Room #162	100	1	PLATES	
52	Room #162	1,600	1	WSS-120	Requires Combination 4 x 4 GFI/Switch Device Cover Plate
52	Room #162	1,600	5	UDF-T8-QXPS-UNV	
52.1	Room #162	500	1	UDF-T8-QXPS-UNV	Restroom
52.2	Room #162	1,600	1	CSS-120	DT200 - Corner Mount Sensor w/ Photocell
52.2	Room #162	1,600	4	BDFWW/N-T8-QXPS-UNV	
52.3	Room #162	1,600	4	NO UPGRADE DUPLICATE	
52.3	Room #162	1,600	1	PHOTO	
53	Corridor	3,000	7	UDF-T8-QXPS-UNV	

Johnson Controls
© Johnson Controls, Inc. Do not copy (physically, electronically or in any other media) without the express written consent of Johnson Controls, Inc.

54	1/2 of Cafeteria	1,650	9	NOUPGRADE-2'2LT5	Existing 2 x 2 2L 24W T5 Direct/Indirect
54	1/2 of Cafeteria	1,650	6	NOUPGRADE-32WCF	Existing 1 x 32W CF Recessed Can
54	1/2 of Cafeteria	1,650	2	CSS-120	W1000A
54.1	1/2 of Cafeteria	8,760	1	VSS-120	
54.1	1/2 of Cafeteria	8,760	1	NOUPGRADE-VENDINGMACHINE	Coke Machine
55	2nd Half of Cafeteria	1,650	6	NOUPGRADE-32WCF	Existing 1 x 32W CF Recessed Can
55	2nd Half of Cafeteria	1,650	2	CSS-120	W1000A
55	2nd Half of Cafeteria	1,650	11	NOUPGRADE-2'2LT5	Existing 2 x 2 2L 24W T5 Direct/Indirect
56	Corridor Outside Cafeteria	3,750	11	NOUPGRADE-32WCF	Existing 1 x 32W CF Recessed Can
56	Corridor Outside Cafeteria	3,750	7	NOUPGRADE-2'2LT5	Existing 2 x 2 2L 24W T5 Direct/Indirect Recessed Troffer
57	Men's Room	3,750	4	UDF-T8-QXPS-UNV	
57	Men's Room	3,750	1	WSS-120	DT200 - Requires 4 x 4 Raised GFI Box Plate
57	Men's Room	100	1	PLATES	
58	Women's Room	100	1	PLATES	
58	Women's Room	3,750	4	UDF-T8-QXPS-UNV	No Access
58	Women's Room	3,750	1	WSS-120	DT200 - Requires 4 x 4 Raised GFI Box Plate
59	Hallway Outside of Green Bean Kitchen	3,750	4	CSS-120	W1000A
59	Hallway Outside of Green Bean Kitchen	3,750	5	NOUPGRADE-32WCF	Existing 1 x 32W CF Recessed Can
59	Hallway Outside of Green Bean Kitchen	3,750	10	NOUPGRADE-2'2LT5	Existing 2 x 2 2L 24W T5 Direct/Indirect Recessed Troffer
60	Division of Juvenile Justics - Office 129	2,250	10	CDF-T8-QLXPS-UNV	
60	Division of Juvenile Justics - Office 129	2,250	2	CSS-120	W1000A
61	Office 129A	2,250	2	CDF-T8-QLXPS-UNV	
61	Office 129A	2,250	1	WSS-120	
62	Division of Juvenile Justice - Office 128	2,250	9	CDF-T8-QLXPS-UNV	
62	Division of Juvenile Justice - Office 128	2,250	2	CSS-120	W1000A
63	2nd Floor - Gymnasium	3,750	20	NOUPGRADE-4'4LT5HO	Existing 2 x 4 4L T5 HO
63	2nd Floor - Gymnasium	3,750	20	FSS-120	
63	2nd Floor - Gymnasium	8,760	1	NOUPGRADE-4'4LT5HO	Existing 2 x 4 4L T5 HO; Night Light
63	2nd Floor - Gymnasium	8,760	1	VSS-120	

Johnson Controls

© Johnson Controls, Inc. Do not copy (physically, electronically or in any other media) without the express written consent of Johnson Controls, Inc.

63	2nd Floor - Gymnasium	8,760	1	NOUPGRADE-VENDINGMACHINE	Coke Machine
63	2nd Floor - Gymnasium	100	2	NO UPGRADE	Multiple Incandescent Stage Lighting; Little or No Use
63.1	2nd Floor - Gymnasium - Above Mezznaine	3,750	2	NOUPGRADE-4'4LT5HO	Existing 2 x 4 4L T5 HO
63.1	2nd Floor - Gymnasium - Above Mezznaine	3,750	2	FSS-120	
64	Rear Stage Entry	8,760	2	BDFWW/N-T8-QLXPS-UNV	
64	Rear Stage Entry	8,760	1	CSS-277	W500A
65	Pete's Place Open Area	1,600	3	CDF-T8-QLXPS-UNV	
66	Office	1,000	1	CDF-T8-QLXPS-UNV	
67	Office	1,000	1	CDF-T8-QLXPS-UNV	
68	Office	1,600	2	CDF-T8-QLXPS-UNV	
68	Office	1,600	1	WSS-277	
68.1	Office - Paper Storage Area	1,000	1	UDF-T8-QLXPS-UNV	
69	Play Area	1,000	3	CDF-T8-QLXPS-UNV	
69	Play Area	1,000	1	WSS-277	WI200 w/ Photocell
69	Play Area	1,000	3	NO UPGRADE DUPLICATE	
69	Play Area	1,000	1	PHOTO	
70	Conference Area	1,000	3	CDF-T8-QLXPS-UNV	
70	Conference Area	1,000	1	WSS-277	
71	Office 252	100	1	PLATES	
71	Office 252	2,250	4	UDF-T8-QLXPS-UNV	
71	Office 252	2,250	1	WSS-277	Requires 4 x 4 Square Raised Device Box Plate
73	Seacoast Hospice Hallway Area	1,600	3	CDF-T8-QLXPS-UNV	
74	Seacoast Hospice Conference Area	1,000	1	WSS-277	
74	Seacoast Hospice Conference Area	1,000	6	CDF-T8-QLXPS-UNV	60 FC Average
75	Hospice Office	1,600	2	CDF-T8-QLXPS-UNV	
75	Hospice Office	1,600	1	WSS-277	
76	Conference Room	1,000	2	CDF-T8-QLXPS-UNV	
76	Conference Room	1,000	1	CSS-277	CX105
77	Electrical Room	500	1	A-T8-QLSS-UNV	
77.1	Senior Center Kitchen	1,600	2	CDF-T8-QLXPS-UNV	
77.1	Senior Center Kitchen	1,600	2	UDF-T8-QXPS-UNV	
77.1	Senior Center Kitchen	1,600	1	WSS-277	
78	Room 233 - Restroom	500	1	UDF-T8-QXPS-UNV	
79	Room 229 - Restroom	500	1	UDF-T8-QXPS-UNV	

Johnson Controls

© Johnson Controls, Inc. Do not copy (physically, electronically or in any other media) without the express written consent of Johnson Controls, Inc.

80	Activity Room	1,600	8	CDF-T8-QLXPS-UNV	
80	Activity Room	500	9	SLSR3020/D-I75-120	Replacing 75W Incandescent; Dimmable
80	Activity Room	1,600	2	CSS-277	W500A
82	Activity Room	1,600	8	CDF-T8-QLXPS-UNV	
82	Activity Room	500	9	SLSR3020/D-I75-120	Replacing 75W Incandescent; Dimmable
82	Activity Room	1,600	2	CSS-277	W500A
83	Corridor	2,250	6	NOUPGRADE-2'2LT5	Existing 2 x 2 2L 24W T5 Direct/Indirect
83	Corridor	2,250	3	CSS-277	W1000A
84	Corridor	2,250	9	NOUPGRADE-32WCF	Existing 1 x 32W CF Recessed Can
84	Corridor	2,250	8	NOUPGRADE-2'2LT5	Existing 2 x 2 2L 24W T5 Direct/Indirect Recessed Troffer
85	Elevator Alcove	2,250	1	CSS-277	W1000A
85	Elevator Alcove	2,250	5	NOUPGRADE-2'2LT5	Existing 2 x 2 2L 24W T5 Direct/Indirect Recessed Troffer
85	Elevator Alcove	2,250	3	NOUPGRADE-32WCF	Existing 1 x 32W CF Recessed Can
86	Gymnasium Alcove	100	4	NOUPGRADE-4X18WPL	Existing 4 x 18W CF Surface Mount Globe
87	Stairway to Balcony	8,760	3	BADFWW/N-QXPS-UNV	Wide Wrap
87	Stairway to Balcony	8,760	3	FMS-277	
88	Stairwell - Door #6	100	1	NOUPGRADE-32WCF	Existing 6 x 32W CF Pendant Mount Fixture
90	Room 243 - Men's Room	2,250	2	UDF-T8-QXPS-UNV	
90	Room 243 - Men's Room	2,250	1	WSS-DT-277	Dual Tech Wall Sensor
91	Room 241 - Women's Room	2,250	1	WSS-DT-277	Dual Tech Wall Sensor
91	Room 241 - Women's Room	2,250	2	UDF-T8-QXPS-UNV	
93	Room 220 - Conference	1,000	9	NOUPGRADE-2'2LT5	Existing 2 x 2 2L 24W T5 Direct/Indirect Recessed Troffer
93	Room 220 - Conference	1,000	1	CSS-277	W1000A
93	Room 220 - Conference	1,000	6	NOUPGRADE-32WCF	Existing 1 x 32W CF Recessed Can
94	Corridor	2,250	6	NOUPGRADE-2'2LT5	Existing 2 x 2 2L 24W T5 Direct/Indirect Recessed Can
94	Corridor	2,250	2	NOUPGRADE-32WCF	Existing 1 x 32W CF Recessed Can
94	Corridor	2,250	5	NOUPGRADE-32WCF	Existing 4 x 32W CF Surface Mount Fixture
96	Men's Room	1,600	4	UDF-T8-QXPS-UNV	
96	Men's Room	1,600	1	WSS-DT-277	Dual Technology
97	Women's Room	1,600	1	WSS-DT-277	Dual Technology
97	Women's Room	1,600	4	UDF-T8-QXPS-UNV	

Johnson Controls

© Johnson Controls, Inc. Do not copy (physically, electronically or in any other media) without the express written consent of Johnson Controls, Inc.

98	Room 213	1,600	1	CSS-277	
98	Room 213	1,600	6	CDF-T8-QLXPS-UNV	
99	Elevator Alcove	2,250	2	NOUPGRADE-2'2LT5	Existing 2 x 2 2L 24W T5 Direct/Indirect
99	Elevator Alcove	2,250	1	NOUPGRADE-4X18WPL	Existing 4 x 18W CF Surface Mount Fixture
100	Room 201 - Open Office	1,600	5	CDF-T8-QLXPS-UNV	
101	Room 201B	1,600	2	CDF-T8-QLXPS-UNV	
101	Room 201B	1,600	1	WSS-277	
102	Room 209A - Activity Room	1,000	6	CDF-T8-QLXPS-UNV	
102	Room 209A - Activity Room	1,000	1	CSS-277	W1000A
103	Room 209	1,000	1	CSS-277	W1000A
103	Room 209	1,000	6	CDF-T8-QLXPS-UNV	
104	Room 208B	1,600	3	CDF-T8-QLXPS-UNV	
104	Room 208B	1,600	1	CSS-277	CX105
105	Small Hallway	1,600	2	CDF-T8-QLXPS-UNV	
106	Room 208A	1,600	1	CSS-277	CX105
106	Room 208A	1,600	3	CDF-T8-QLXPS-UNV	
106	Room 206B	1,600	6	CDF-T8-QLXPS-UNV	
106	Room 206B	1,600	1	CSS-277	W1000A
107	Small Hallway	1,600	2	CDF-T8-QLXPS-UNV	
108	Room 206A	1,600	3	CDF-T8-QLXPS-UNV	
108	Room 206A	1,600	1	CSS-277	
109	Office 205	1,600	2	CDF-T8-QLXPS-UNV	
110	Office 205A	1,600	2	CDF-T8-QLXPS-UNV	
110	Office 205A	1,600	1	WSS-277	WI200 w/ Photocell
110	Office 205A	1,600	2	NO UPGRADE DUPLICATE	
110	Office 205A	1,600	1	PHOTO	
111	Office 203	1,600	1	CSS-277	CX105
111	Office 203	1,600	3	CDF-T8-QLXPS-UNV	
112	Room 202 - Copy Room	1,600	1	BDFWW/N-T8-QLXPS-UNV	
112	Room 202 - Copy Room	1,600	1	WSS-277	
113	Central Stairwell	8,760	2	BDFWW/N-T8-QLXPS-UNV	
113	Central Stairwell	8,760	2	FMS-277	
113	Central Stairwell	8,760	1	BDFWW/N-T8-QLXPS-UNV	
114	Long Hallway	1,800	10	NOUPGRADE-2'2LT5	Existing 2 x 2 2L 24W T5 Direct/Indirect Recessed Toffer
115	3rd Floor - Room 302A	2,000	4	UDF-T8-QXPS-UNV	

Johnson Controls

© Johnson Controls, Inc. Do not copy (physically, electronically or in any other media) without the express written consent of Johnson Controls, Inc.

115	3rd Floor - Room 302A	2,000	1	CSS-277	W1000A
116	Room 301- Computer Lab	1,600	9	UDF-T8-QXPS-UNV	
116	Room 301- Computer Lab	1,600	1	CSS-277	W1000A
117	Corridor	2,000	6	NOUPGRADE-2'2LT5	Existing 2 x 2 2L 24W T5 Direct/Indirect Recessed Toffer
118	Elevator Alcove	2,000	4	NOUPGRADE-2'2LT5	Existing 2 x 2 2L 24W T5 Direct/Indirect Recessed Toffer
118	Elevator Alcove	2,000	3	NOUPGRADE-4X18WPL	Existing 4 x 18W CF Surface Mount Fixture
118	Elevator Alcove	2,000	1	CSS-277	W1000A
119	Room 309	1,000	3	CDF-T8-QLXPS-UNV	
119	Room 309	1,000	1	CSS-277	W500A
120	Men's Room	2,250	3	UDF-T8-QXPS-UNV	
120	Men's Room	2,250	1	WSS-DT-277	Require 4 x 4 Raised GFI Box Cover
120	Men's Room	100	1	PLATES	
121	Women's Room	2,250	3	UDF-T8-QXPS-UNV	
121	Women's Room	2,250	1	WSS-DT-277	Require 4 x 4 Raised GFI Box Cover
121	Women's Room	100	1	PLATES	
122	Corridor	2,250	3	NOUPGRADE-2'2LT5	Existing 2 x 2 2L 24W T5 Direct/Indirect Recessed Toffer
123	Corridor	2,250	3	NOUPGRADE-2'2LT5	Existing 2 x 2 2L 24W T5 Direct/Indirect Recessed Toffer
124	Corridor	2,250	8	NOUPGRADE-2'2LT5	Existing 2 x 2 2L 24W T5 Direct/Indirect Recessed Toffer
125	Room 321	1,200	9	CDF-T8-QLXPS-UNV	
125	Room 321	1,200	1	CSS-277	W1000A
126	Office	2,250	3	CDF-T8-QLXPS-UNV	
127	Room 323	2,250	6	CDF-T8-QLXPS-UNV	
127	Room 323	2,250	1	CSS-277	W1000A
128	Men's Room	1,000	1	WSS-DT-277	
128	Men's Room	1,000	2	UDF-T8-QXPS-UNV	
129	Room 327 - Women's Room	1,000	2	UDF-T8-QXPS-UNV	
129	Room 327 - Women's Room	1,000	1	WSS-DT-277	
130	Room 328	1,600	4	CDF-T8-QLXPS-UNV	
130	Room 328	1,600	1	CSS-277	W1000A
131	Room 330	2,250	12	BDF-T8-QXPS-UNV	Existing 4L T8
131	Room 330	2,250	2	CSS-277	W1000A

Johnson Controls

© Johnson Controls, Inc. Do not copy (physically, electronically or in any other media) without the express written consent of Johnson Controls, Inc.

132	Office 331	2,250	2	CSS-277	W1000A
132	Office 331	2,250	12	BDF-T8-QXPS-UNV	Existing 4L T8
133	Room 332	2,250	12	BDF-T8-QXPS-UNV	Existing 4L T8
133	Room 332	2,250	2	CSS-277	W1000A
134	Long Corridor	2,250	7	NOUPGRADE-2'2LT5	Existing 2 x 2 2L 24W T5 Direct/Indirect Recessed Toffer
134	Long Corridor	2,250	16	NOUPGRADE-32WCF	Existing 1 x 32W CF Recessed Can
134	Long Corridor	2,250	4	NOUPGRADE-4X18WPL	Existing 4 x 18W CF Surface Mount Fixture
135	Elevator Alcove	2,250	6	NOUPGRADE-2'2LT5	Existing 2 x 2 2L 24W T5 Direct/Indirect Recessed Toffer
135	Elevator Alcove	2,250	2	NOUPGRADE-32WCF	Existing 1 x 32W CF Recessed Can
135	Elevator Alcove	2,250	2	CSS-277	W500A
136	Room 346	1,000	8	CDF-T8-QLXPS-UNV	No Access
136	Room 346	1,000	1	CSS-277	W1000A
137	Room 334	2,250	9	CDF-T8-QLXPS-UNV	No Access
138	Open Office	2,250	7	BDF-T8-QXPS-UNV	
139	Food Pantry	2,250	2	BDF-T8-QXPS-UNV	
139	Food Pantry	2,250	1	WSS-277	
140	Men's Room	2,250	3	UDF-T8-QXPS-UNV	
140	Men's Room	2,250	1	WSS-DT-277	
141	Women's Room	2,250	3	UDF-T8-QXPS-UNV	
141	Women's Room	2,250	1	WSS-DT-277	
142	Room 341	1,000	3	CDF-T8-QLXPS-UNV	
142	Room 341	1,000	1	CSS-277	CX105
143	Office 344	1,000	1	CDF-T8-QLXPS-UNV	
144	Office 343	1,000	1	CDF-T8-QLXPS-UNV	
145	Conference Room 342	1,000	4	ADFW/N-T8-QXPS-UNV	
145	Conference Room 342	1,000	1	WSS-277	
146	Door #7 Stairwell	8,760	5	FMS-277	
146	Door #7 Stairwell	8,760	5	ADFWW/N-T8-QXPS-UNV	20' Above Stairwell Landing
147	Door #8 Stairwell	8,760	5	FMS-277	
147	Door #8 Stairwell	8,760	5	ADFWW/N-T8-QXPS-UNV	20' Above Stairwell Landing
148	Door #2 Stairwell	8,760	5	ADFWW/N-T8-QXPS-UNV	20' Above Stairwell Landing
148	Door #2 Stairwell	8,760	5	FMS-277	
149	4th Floor - Elevator Office	2,250	2	CDFT-T8-QLXPS-UNV	

Johnson Controls
© Johnson Controls, Inc. Do not copy (physically, electronically or in any other media) without the express written consent of Johnson Controls, Inc.

149	4th Floor - Elevator Office	2,250	1	CDF-T8-QLXPS-UNV	
150	Room 410 - Kitchenette	1,600	2	CDF-T8-QLXPS-UNV	
150	Room 410 - Kitchenette	1,600	1	WSS-277	
151	Room 411 - Men's Room	2,250	1	UDF-T8-QXPS-UNV	
151	Room 411 - Men's Room	2,250	1	WSS-DT-120	
152	Room 412 - Women's Room	2,250	2	UDF-T8-QXPS-UNV	
152	Room 412 - Women's Room	2,250	1	WSS-DT-120	
153	Room 401 - Open Office	2,250	3	CDF-T8-QLXPS-UNV	
154	Conference Room	1,000	1	CDF-T8-QLXPS-UNV	
155	Office	2,250	2	CDF-T8-QLXPS-UNV	
155	Office	2,250	1	WSS-277	WI200 w/ Photo
155	Office	2,250	2	NO UPGRADE DUPLICATE	
155	Office	2,250	1	PHOTO	
156	Office	2,250	3	CDF-T8-QLXPS-UNV	
157	Conference Room	1,000	12	NOUPGRADE-32WCF	Existing 1 x 32W CF Recessed Can
157	Conference Room	1,000	2	NOUPGRADE-8'6LT8	Existing 8' 6L T8 Architectural Uplight
158	Office	2,250	3	CDF-T8-QLXPS-UNV	
159	Superintendent's Office	2,250	3	NOUPGRADE-4'4LT5HO	Existing 2 x 4 4L T5 Avante-Style Fixture
159	Superintendent's Office	2,250	1	CSS-277	W1000A
160	Office 403	2,250	6	CDF-T8-QLXPS-UNV	
161	Conference Room/Office	2,250	3	NOUPGRADE-4'4LT5HO	Existing 2 x 4 4L T5 Avante-Style Fixture
161	Conference Room/Office	2,250	1	CSS-277	
162	Office 405	2,250	6	CDF-T8-QLXPS-UNV	
163	Office	2,250	1	CDF-T8-QLXPS-UNV	
164	Office	2,250	2	NOUPGRADE-4'4LT5HO	Existing 2 x 4 4L T5 Avante-Style Fixture
164	Office	2,250	1	WSS-277	
165	Room 406 - Copy Area	2,250	3	ADFW/N-T8-QXPS-UNV	
165	Room 406 - Copy Area	2,250	2	CDF-T8-QLXPS-UNV	
165	Room 406 - Copy Area	2,250	1	CSS-277	CX105
165	Room 406 - Small Hallway	1,000	1	CDF-T8-QLXPS-UNV	
166	Conference Room/Kitchen Area	1,600	1	CSS-277	
166	Conference Room/Kitchen Area	1,600	4	CDF-T8-QLXPS-UNV	
167	Room 413 - Hall	2,250	3	UDF-T8-QXPS-UNV	
167	Room 413 - Hall	2,250	1	CSS-277	CX105
168	Room 416	1,000	3	BDFWW/N-T8-QXPS-UNV	

Johnson Controls
© Johnson Controls, Inc. Do not copy (physically, electronically or in any other media) without the express written consent of Johnson Controls, Inc.

168	Room 416	1,000	1	WSS-277	Requires 4 x 4 Raised GFI Box Cover
168	Room 416	100	1	PLATES	
168	Room 415	100	1	NOUPGRADE-4'2L32WT8NP	Existing 4' 2L T8 Strip Fixrture w/ Wire Guard
168	Room 415	100	1	WIRE GUARD	
168	Room 414 - Custodial	100	1	WIRE GUARD	
168	Room 414 - Custodial	100	1	NOUPGRADE-4'2L32WT8NP	Existing 4' 2L T8 Strip Fixrture w/ Wire Guard
169	Corridor	2,250	4	NOUPGRADE-2'2LT5	Existing 2 x 2 2L 24W T5 Direct/'Indirect Recessed Troffer
169	Corridor	100	3	NOUPGRADE-4X18WPL	Existing 4 x 18W CF Surface Mount Fixtures
169	Door #3 Stairwell	8,760	7	BDFWW/N-QXPS-UNV	(1) @ 20' Above Stairwell Landing
169	Door #3 Stairwell	8,760	7	FMS-277	
170	Door #5 Stairwell	8,760	7	BDFWW/N-QXPS-UNV	(1) @ 20' Above Stairwell Landing
170	Door #5 Stairwell	8,760	7	FMS-277	
171	Exterior	3,650	2	NOUPGRADE-MH400	Façade Lighting; 2" Slip Fitter
171	Exterior	3,650	5	NO UPGRADE	MH175 Wall Wash Fixture
171	Exterior	3,650	6	NO UPGRADE	Existing CF Surface Mount Over Doors
171	Exterior	3,650	2	NO UPGRADE	Existing CF Wall Wash Near Door #6
171	Exterior	3,650	3	NOUPGRADE-MH50	Existing MH50 w/ Photocell Near Door #6
171	Exterior	3,650	1	NOUPGRADE-MH400	Flag Flood Light

Johnson Controls

© Johnson Controls, Inc. Do not copy (physically, electronically or in any other media) without the express written consent of Johnson Controls, Inc.